



NOTES

1. PIPE SHALL BE FULLY SUPPORTED FOR ITS ENTIRE LENGTH WITH APPROPRIATE COMPACTION UNDER PIPE HAUNCHES.
2. TRENCH SHALL BE DRY DURING PLACEMENT
3. BACKFILL SHALL BE FREE OF UNSUITABLE MATERIAL SUCH AS LARGE ROCK, MUCK, STICKS, ROOTS & OTHER DEBRIS.
4. ALL BACKFILL SHALL BE COMPACTED TO A MINIMUM OF 95% DENSITY OF AASHTO T-180 MODIFIED PROCTOR.

TYPICAL TYPE 3 TRENCH DETAIL