## Volusia County Fire Rescue Minimum Requirements for Final Inspection

- Addressing
- Mechanical all new duct detectors shall be tested with smoke
- o Knox box (new buildings) shall be mounted and have the following placed inside of the box. One key to the main entrance.
- o All mechanical and electrical rooms
- Emergency elevator operations (2)
- o Fire alarm panel
- Pull stations
- Business card of 24/7 emergency point of contact
- o Electrical panel schedule, spares in the off position
- Signage stairwells, mechanical, electrical, exits
- Lighting emergency
- o Extinguishers quantity, type, location
- Prior to final approval of construction, it is the responsibility of the property owner or designee to ensure 100% radio/cellular communication capabilities for all fire and police personnel in accordance with NFPA 72, Chapter 24, Paragraph 24.5.2 Two-Way Radio Communications Enhancement Systems. If a failure occurs, a radio/cellular enhancement system will need to be installed.
- Fire sprinkler contractor
- o Below ground testing certificate
- Above ground testing certificate
- o Fire pump testing certificate (new buildings)
- o An original copy (non-copy machine) of NFPA 13
- Hydraulic plates
- Spare heads and associated wrenches
- o Escutcheons/cover plates
- Copy of plans 4 inch PVC by fire alarm control panel (FACP)
- o Maintenance contract
- o Signage

## Fire Alarm Contractor

- o Location of electrical panel and breaker associated with the panel
- o Contact number inside of the panel door
- o Account number inside of the panel door
- o All strobes within visual of another shall be in synchronization
- o Record of completion
- Monitoring contract
- o Maintenance contract
- o Copy of plans 4 inch PVC by FACP

## Fire Suppression Contractor

**UL-300** 

- Notification device
- o Gas company representative
- Electrical Inspector
- Representative of the business (owner/chef)

- o Chain
- o Shunt trip
- o Chocks
- o Pre-Engineered Restaurant Fire Suppression Systems Report.
- o Signage

## FM-200

- o Notification device
- o Fan test Enclosure Integrity Report
- o Signage